

OFFICE OF THE FULTON COUNTY ENGINEER

Frank T. Onweller, P.E., P.S.,
County Engineer

Rod Creager, P.E., P.S.,
Chief Deputy Engineer

**BID QUANTITY TABULATIONS
PROJECT: CHESTERFIELD TOWNSHIP 2007 ASPHALT RESURFACING**

June 4, 2007

ENGINEERS

Gerken Paving, Inc.

REF. NO.	ITEM NO.	QUANTITY	UNITS	DESCRIPTION	UNIT PRICE	ESTIMATED COST	UNIT PRICE	ESTIMATED COST
Road 16 from Road J to Road K Existing: 5,500' X 18' Widening, Leveling and surface course								
1	202	124	S.Y.	Pavement grinding of Butt Joints.....	\$ 15.00	\$ 1,860.00	\$ 14.50	\$ 1,798.00
2	448	450	C.Y.	Asphalt Concrete, Type1 PG 64 - 22 leveling to be placed at 1 1/2"	\$ 97.00	\$ 43,650.00	\$ 96.00	\$ 43,200.00
3	448	450	C.Y.	Asphalt Concrete, Type1 PG 64 - 22 surface to be placed at 1 1/2"	\$ 97.00	\$ 43,650.00	\$ 96.00	\$ 43,200.00
4	407	2,160	GAL.	Tack Coat..... Application rate @ 0.10 Gal/S.Y.	\$ 1.10	\$ 2,376.00	\$ 1.00	\$ 2,160.00
INCIDENTALS								
5	614	1	Lump	Maintenance of Traffic.....	\$ 1,000.00	\$ 1,000.00	\$ 2,000.00	\$ 2,000.00
TOTAL AMOUNT OF BID:						\$ 92,536.00		\$ 92,358.00
								-0.19%
						% difference from Engineer's estimate:		