

OFFICE OF THE FULTON COUNTY ENGINEER

Frank T. Onweller, P.E., P.S.,
County Engineer

Rod Creager, P.E., P.S.,
Chief Deputy Engineer

BID QUANTITY TABULATIONS

PROJECT: DOVER TOWNSHIP - Road 17 Asphalt Resurfacing

July 2, 2008

ENGINEERS

Gerken Paving, Inc.

REF. NO.	ITEM NO.	QUANTITY	UNITS	DESCRIPTION	UNIT PRICE	ESTIMATED COST	UNIT PRICE	ESTIMATED COST
Road 17 from Road J to Road K Existing: 5,625' X 18.5'								
1	202	120	S.Y.	Pavement grinding of Butt Joints.....	\$ 15.50	\$ 1,860.00	\$ 11.00	\$ 1,320.00
2	407	3,412	GAL.	Tack Coat..... Application rate @ 0.10 Gal/S.Y	\$ 1.00	\$ 3,412.00	\$ 1.00	\$ 3,412.00
3	448	239	C.Y.	Asphalt Concrete, Type 1 Interm. Course..... scratch leveling	\$ 135.00	\$ 32,265.00	\$ 141.00	\$ 33,699.00
4	448	400	C.Y.	Asphalt Concrete, Type 1 Interm. Course..... PG 64 - 22; to be placed at 1 1/4"	\$ 135.00	\$ 54,000.00	\$ 141.00	\$ 56,400.00
5	448	400	C.Y.	Asphalt Concrete, Surface Course..... PG 64 - 22; ; to be placed at 1 1/4"	\$ 135.00	\$ 54,000.00	\$ 141.00	\$ 56,400.00
6	special	11,375	S.Y.	Fiberglass / Polyester Interlayer	\$ 3.00	\$ 34,125.00	\$ 3.05	\$ 34,693.75
7	617	206	C.Y.	Aggregate Shoulder (1.5' x 4.00"). Material: O.D.O.T. 411; limestone	\$ 38.00	\$ 7,828.00	\$ 36.50	\$ 7,519.00
INCIDENTALS								
8	614	1	Lump	Maintenance of Traffic.....	\$ 2,500.00	\$ 2,500.00	\$ 6,200.00	\$ 6,200.00
TOTAL AMOUNT OF BID:						\$ 189,990.00		\$ 199,643.75
						% difference from Engineer's estimate:		5.08%