

**OFFICE OF THE FULTON COUNTY ENGINEER**

Frank T. Onweller, P.E., P.S.,  
County Engineer

Rod Creager, P.E., P.S.,  
Chief Deputy Engineer

**BID QUANTITY TABULATIONS  
PROJECT: FULTON TOWNSHIP 2008 ROAD J ASPHALT RESURFACING**

April 7, 2008

REF. NO.	ITEM NO.	QUANTITY	UNITS	DESCRIPTION	ENGINEERS		GERKEN PAVING, INC.		HENRY W. BERGMAN, INC.	
					UNIT PRICE	ESTIMATED COST	UNIT PRICE	ESTIMATED COST	UNIT PRICE	ESTIMATED COST
<b>Road J Road 1 to St. Rt. 64 5604' X 18.0' widening, leveling and surface overlay</b>										
1	202	60	S.Y.	Pavement grinding of Butt Joints.....	\$ 15.00	\$ 900.00	\$ 15.50	\$ 930.00	\$ 10.00	\$ 600.00
2	202	137	C.Y.	2.0 Trench Widening south side only; depth of 4"	\$ 30.00	\$ 4,110.00	\$ 29.00	\$ 3,973.00	\$ 35.00	\$ 4,795.00
3	204	1245	S.Y.	Subgrade Compaction trench widening area	\$ 0.75	\$ 933.75	\$ 0.30	\$ 373.50	\$ 1.00	\$ 1,245.00
4	301	137	C.Y.	Asphalt Concrete, base material	\$ 100.00	\$ 13,700.00	\$ 104.00	\$ 14,248.00	\$ 100.00	\$ 13,700.00
5	448	360	C.Y.	Asphalt Concrete, Type1 PG 64 - 22 surface scratch leveling course for slope adjustment	\$ 98.50	\$ 35,460.00	\$ 102.00	\$ 36,720.00	\$ 100.00	\$ 36,000.00
6	448	332	C.Y.	Asphalt Concrete, Type1 PG 64 - 22 surface to be placed at 1"	\$ 98.50	\$ 32,702.00	\$ 102.00	\$ 33,864.00	\$ 110.00	\$ 36,520.00
7	407	2,614	GAL.	Tack Coat..... Application rate @ 0.10 Gal/S.Y.	\$ 1.10	\$ 2,875.40	\$ 1.00	\$ 2,614.00	\$ 1.50	\$ 3,921.00
<b>INCIDENTALS</b>										
8	614	1	Lump	Maintenance of Traffic.....	\$ 1,500.00	\$ 1,500.00	\$ 3,250.00	\$ 3,250.00	\$ 2,500.00	\$ 2,500.00
<b>TOTAL AMOUNT OF BID:</b>					\$ 92,181.15		\$ 95,972.50		\$ 99,281.00	
					% difference from Engineer's estimate:		4.11%		7.70%	