

OFFICE OF THE FULTON COUNTY ENGINEER

Frank T. Onweller, P.E., P.S.,
County Engineer

Rod Creager, P.E., P.S.,
Chief Deputy Engineer

9120 Co. Rd. 14
Wauseon, OH 43567-9669
Telephone: 419-335-3816 Fax: 419-335-1091

| BIDDERS TABULATION | | | | | | | | | | ENGINEER'S | Gerken Paving, Inc. | The Shelly Company | Geddis Paving & Exc., Inc. |
|---|----------|----------|-------|---|--------------|----------------------|--|----------------------|----------------------|----------------|---------------------|--------------------|----------------------------|
| PROJECT: Fulton County Road A Resurfacing (4 to 10) | | | | | | | | | | \$374,408.00 | \$338,719.10 | \$356,942.40 | \$368,866.75 |
| BID DATE: March 27, 2008 | | | | | | | | | | | -9.5% | -4.7% | -1.5% |
| REF. NO. | ITEM NO. | QUANTITY | UNITS | DESCRIPTION | UNIT PRICE | ESTIMATED COST | UNIT PRICE | ESTIMATED COST | UNIT PRICE | ESTIMATED COST | UNIT PRICE | ESTIMATED COST | |
| 1 | 202 | 1,794 | SY | Pavement Removed for Butt-Joints and Asphalt Drives..... | \$ 15.00 | \$ 26,910.00 | \$ 4.00 | \$ 7,176.00 | \$ 5.00 | \$ 8,970.00 | \$ 7.00 | \$ 12,558.00 | |
| 2 | 407 | 6,324 | GAL | Tack Coat @ 0.10 Gal/SY..... | \$ 1.25 | \$ 7,905.00 | \$ 1.00 | \$ 6,324.00 | \$ 0.85 | \$ 5,375.40 | \$ 1.75 | \$ 11,067.00 | |
| 3 | 448 | 2,659 | CY | Asphalt Conc., Intermediate Course, Type 1, PG 64-22, Th. = 1.25-In (Calculated at 1.5-In)..... | \$ 102.00 | \$ 271,218.00 | \$ 102.40 | \$ 272,281.60 | \$ 112.00 | \$ 297,808.00 | \$ 111.50 | \$ 296,478.50 | |
| 4 | 448 | 32 | CY | Asphalt Conc., Interm. Course for Intersections and Drives, Type 1, PG 64-22 , Th. = 1.25-In..... | \$ 300.00 | \$ 9,600.00 | \$ 290.00 | \$ 9,280.00 | \$ 112.00 | \$ 3,584.00 | \$ 145.00 | \$ 4,640.00 | |
| 5 | 614 | 1 | LS | Maintenance of Traffic..... | \$ 12,000.00 | \$ 12,000.00 | \$ 11,200.00 | \$ 11,200.00 | \$ 6,000.00 | \$ 6,000.00 | \$ 4,450.00 | \$ 4,450.00 | |
| 6 | 617 | 785 | CY | Reconditioning of Shoulders, (Avg. 2-In x 2 ft), ODOT 411 Limestone..... | \$ 45.00 | \$ 35,325.00 | \$ 29.50 | \$ 23,157.50 | \$ 33.00 | \$ 25,905.00 | \$ 38.25 | \$ 30,026.25 | |
| 7 | 642 | 13.0 | MI | Edge Line, Type 1..... | \$ 525.00 | \$ 6,825.00 | \$ 400.00 | \$ 5,200.00 | \$ 400.00 | \$ 5,200.00 | \$ 415.00 | \$ 5,395.00 | |
| 8 | 642 | 6.0 | MI | Centerline, Type 1..... | \$ 650.00 | \$ 3,900.00 | \$ 600.00 | \$ 3,600.00 | \$ 600.00 | \$ 3,600.00 | \$ 622.00 | \$ 3,732.00 | |
| 9 | 642 | 2 | EA | Railroad Symbol Marking, Type 1..... | \$ 362.50 | \$ 725.00 | \$ 250.00 | \$ 500.00 | \$ 250.00 | \$ 500.00 | \$ 260.00 | \$ 520.00 | |
| TOTAL BID..... | | | | | | \$ 374,408.00 | \$ 338,719.10 | \$ 356,942.40 | \$ 368,866.75 | | | | |
| | | | | | | | % Difference From Engineer's Estimate: | -9.5% | -4.7% | -1.5% | | | |