

OFFICE OF THE FULTON COUNTY ENGINEER

9120 County Road 14
Wauseon, Ohio 43567-9669

Telephone: 419-335-3816

www.fultoncountyoh.com/engineer.htm

Fax: 419-335-1091

Frank T. Onweller, P.E., P.S.
County Engineer

Rod Creager, P.E., P.S.
Chief Deputy Engineer

June 5, 2013

ADDENDUM 1

2013 Reclamation of Various Fulton County Roads

RE: Prevailing Wage Rates, Adjusted Unit Price Bid Schedule, Typical Sections, Clarification

1. Prevailing Wage Rates

Permanently attach the two updated Prevailing Wage Rates to the proposal.

2. Adjusted Unit Price Bid Schedule

There are quantity changes to Reference Numbers 36-43 in the Clinton Township Road B portion of the Unit Price Bid Schedule. Permanently attach the updated page 8 and 9 to the proposal. There is no change to the cost estimate.

3. Typical Sections

Note that on page 31, in the legend for Road B (Road AC to SR108), the shoulder should be listed as 2.0'x2.5".

4. Clarification

Railroad Protective Liability Insurance is not to be included in the bid. All work will be outside the railroad right of way limits.

End of addendum.

REF. NO.	ITEM NO.	QUANTITY	UNITS	DESCRIPTION	UNIT PRICE	ESTIMATED COST
Fulton County Road 3 ~ Road H to Railroad Continued						
25	448	243	C.Y.	Asphalt Concrete, Intermediate Course, Type 2.....	\$	\$
26	448	162	C.Y.	Asphalt Concrete, Surface Course, Type 1.....	\$	\$
27	617	34	C.Y.	Aggregate Shoulder.....	\$	\$
28	614	1	LUMP	Maintaining Traffic.....	\$	\$
Royalton Township Road N ~ SR109 to Road 8						
29	Special	206	TON	Portland Cement.....	\$	\$
30	Special	11,744	S.Y.	Full Depth Reclamation.....	\$	\$
31	409	4,757	GAL.	Bituminous Material: HFRS2.....	\$	\$
32	409	132	C.Y.	Washed No. 8 Cover Aggregate.....	\$	\$
33	Special	1,270	S.Y.	Bituminous Fog Seal Material.....	\$	\$
34	642	1	MILE	Centerline, Type 1.....	\$	\$
35	614	1	LUMP	Maintaining Traffic.....	\$	\$
Clinton Township Road B ~ Road AC to SR108						
36	202	105	S.Y.	Pavement Removed for Buttjoints.....	\$	\$
37	Special	12,510	S.Y.	Full Depth Reclamation.....	\$	\$
38	Special	200	TON	Portland Cement.....	\$	\$
39	408	4,379	GAL.	Prime Coat.....	\$	\$

REF. NO.	ITEM NO.	QUANTITY	UNITS	DESCRIPTION	UNIT PRICE	ESTIMATED COST
Clinton Township Road B ~ Road AC to SR108 Continued						
40	408	94	TON	Choke Aggregate.....	\$ _____	\$ _____
41	407	1,000	GAL.	Tack Coat.....	\$ _____	\$ _____
42	448	675	C.Y.	Asphalt Concrete, Intermediate Course, Type 2.....	\$ _____	\$ _____
43	617	170	C.Y.	Aggregate Shoulder.....	\$ _____	\$ _____
44	614	1	LUMP	Maintaining Traffic.....	\$ _____	\$ _____
INCIDENTALS						
45	103	1	LUMP	Premium for Contract Performance & Maintenance Guarantee Bond	\$ _____	\$ _____

TOTAL AMOUNT OF BID: _____

in submitting the Bid, the Bidder represents, that the Bidder has examined and carefully studied the Bidding Documents, and the other related data identified in the Bidding Documents, and the following Addenda, receipt of all, which is hereby acknowledged.

<u>Addendum No.</u>	<u>Addendum Date</u>
_____	_____
_____	_____

Respectfully Submitted:

Attest: _____
Corporation Seal

_____ Company

_____ Date

_____ By _____ Title